Bruhat Bangalore Mahanagara Palike
Executive Engineer Yelahanka Division

Name of work: Improvements To Roads and Drains At Attur Layout Surrounding Areas in Ward No-03

Modified Schedule - B

Sl No	Description of Item	Unit	Quantity	Rate, Rs	
				In Figures	In Words
1	KSRRB 300-2. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications	Cum	1085.47	160.00	Rupees One Hundred Sixty Only
2	KSRB 4-2.3 : Providing and laying in position plain cement concrete of Mix 1:4:8 with OPC @ 280kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 25 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM curing complete as per specifications.	Cum	143.94	5500.00	Rupees Five Thousand Five Hundred Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 2500, 2700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm	Cum	296.98	5700.00	Rupees Five Thousand Seven Hundred Only
4	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM complete as per specifications.	Tn	19.55	75800.00	Rupees Seventy Five Thousand Eight Hundred Only
5	Providing and Fixing pre cast covering Slab 100mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)	Sqm	559.40	2600.00	Rupees Two Thousand Six Hundred Only

SURVEYING SERVICES

Description of Item	Unit	Quantity	Rate, Rs	
			In Figures	In Words
ng and fixing RCC precast cover slab of 250mm or drain in cement concrete 1:1.5:3 using graded te jelly 20mm and down size with steel forcement, including form work, lift charges, curing concrete finished surfaces on both sides etc, mplete and as per drawing and the directions of ngineer in-charge. (Data Rate)	Sqm	20.05	5600.00	Rupees Five Thousand Six Hundred Only

Executive Engineer,
Yelahanka Division,
BBMP Bangalore

Executive Engineer,
Yelahanka Division,
B.B.M.P, Bangalore - 64